NOTES:
1 Final spacing, quantitiy, tree species to the satisfaction of the General Manager of Engineering Services. New trees must be of good standard, 75mm minimum caliper, and installed with approved root barriers, tree guards and appropriate soil.
Root barriers shall be 8'-0" long and 18" deep. Planting depth of rootball must be below sidewalk grade. New trees to be provided adjacent to the development site, to be confirmed prior to the issuance of the occupany permit.
Call Park Board for inspecton after tree planting completion.
2 High efficiency automatic irrigation system is to be provided for all landscape areas over parking structure
3 Hose bibs located on patio, one per unit. Refer to architecture for locations.
4 Refer to architecture for all hardscape - paving, retaining walls, fences and gates and structures.

0 5 10 15 20 25 FT

No.	Date	Revision Notes	Zone	Approvals
A	2/20/12	issued for rezoning		

No.	Date	Issue Notes

Professional Stamp

Design Firm
eta
ockford tyocke & associates landscape architecture

Legal Address

t | 683-1456
f | 683-1459
w | www.etala.ca

1690 West 2nd Avenue
Vancouver . BC . Canada V6J 1H4

All Rights Reserved by ockford tyocke + associates.
This design is not to be used or reproduced without the consent of ockford tyocke + associates.

Project Title
OAK & 46th AVENUE
6170 Oak St.
Vancouver, BC

Drawing Title
LANDSCAPE PLAN:
Planting

Project Manager	
Project ID	21204
Drawn By	CB
Scale	1" = 10'-0"
Reviewed By	DT
Drawing No.	L2.0
Date	01.26.2012
	of 4

Fri, Feb 17, 2012
21204 46th&Oak ReZoning 02.17.2012.vwx